


CLWA PROVIDES WATER TO LOCAL PURVEYORS

CLWA receives and treats surface (“imported”) water from the SWP. The SWP consists of facilities operated by the California Department of Water Resources to conserve and convey water to SWP contractors for use as agricultural or urban supply. CLWA operates two water treatment plants, the Earl Schmidt Filtration Plant (ESFP) in Castaic and the Rio Vista Water Treatment Plant (RVWTP) in Saugus. The SCV’s four water purveyors distribute the treated SWP water. Water quality information for your area is presented in the table contained in this report.

CLWA Santa Clarita Water Division (SCWD) provides water to customers in Bouquet, Soledad and Sand Canyons, and southwest Newhall. Customers received approximately 66% SWP water and 34% local groundwater in 2007. **Los Angeles County Waterworks District #36 (LACWWD #36)** serves customers located in Hasley Canyon and the community of Val Verde. LACWWD #36 provides its own Consumer Confidence Report to its customers. **Newhall County Water District (NCWD)** serves customers located in the Castaic, Newhall, Pinetree and Tesoro del Valle areas. In 2007, Castaic customers received 77% SWP water and 23% local groundwater, Newhall customers received 32% SWP water and 68% local groundwater, and Pinetree customers received 54% SWP water and 46% local groundwater. Tesoro del Valle customers received 100% SWP water. **Valencia Water Company (VWC)** supplies water to customers in Valencia, Stevenson Ranch, and portions of Castaic, Saugus, and Newhall. In 2007, VWC customers received 51% SWP water and 47% local groundwater. In addition, some large landscape customers received 2% recycled water.

Castaic Lake Water Agency Service Area



CHEMICALS IN THE NEWS – PERCHLORATE

Perchlorate, a chemical used in making rocket and ammunitions propellants, has been a water quality concern in the SCV for the past few years. It was detected in 1997 in four Saugus Formation wells operated by the purveyors, near the former Whittaker-Bermite facility. These four wells have not been used as sources of supply since 1997. In November 2002, perchlorate was detected in an Alluvial well adjacent to the Whittaker site, and it was immediately closed.

In 2002, CLWA and the U.S. Army Corps of Engineers signed a cost-sharing agreement for a feasibility study of the area. All proceedings and data are available to the public through a California Department of Toxic Substances Control (DTSC) information repository and public meetings. A notification level of 6 ug/L was determined in early 2004. DPH has adopted 6 ug/L as an MCL for perchlorate since that time.

The purveyors and the DTSC signed an oversight agreement in 2003 regarding studies of treatment technologies for removing perchlorate from water supplies, and have also been working with DPH for the necessary permits for these treatment processes. Treatment method pilot studies were conducted during 2003, and in 2004 CLWA and the purveyors selected ion exchange as the preferred treatment method for removing perchlorate. Design of the CLWA treatment facilities and related pipe-

lines was complete in 2007. Construction of the treatment facility and pipelines began in November 2007 and water will begin being treated in early 2009.

Under federal and state law, the owners of the Whittaker-Bermite property have the responsibility for the groundwater cleanup. A final settlement to remediate and treat the contaminated water was completed and executed by the parties in April 2007.

WATER QUALITY DEFINITIONS

In order to ensure that tap water is safe to drink, the United States Environmental Protection Agency (USEPA) and the California Department of Public Health (DPH) prescribe regulations that limit the amount of certain contaminants in water provided by public water systems. USEPA, DPH and the California Environmental Protection Agency (CalEPA) set goals and legal standards for the quality of drinking water. These standards are intended to protect consumers from contaminants in drinking water. Most of the standards are based on the concentration of contaminants, but a few are based on a Treatment Technique (TT) to remove the contaminant. Drinking water, including bottled water, may reasonably be expected to contain at least small amounts of some contaminants. The presence of contaminants does not necessarily indicate that water poses a health risk. More information about contaminants and potential health effects can be obtained by calling the EPA’s Safe Drinking Water Hotline (1-800-426-4791).

Some people may be more vulnerable to contaminants in drinking water than the general population. Immuno-compromised persons such as persons with cancer undergoing chemotherapy, persons who have undergone organ transplants, people with HIV/AIDS or other immune system disorders, some elderly, and infants can be particularly at risk from infections. These people should seek advice about drinking water from their health care providers. USEPA/Centers for Disease Control (CDC) guidelines on appropriate means to lessen the risk of infection by Cryptosporidium and other microbial contaminants are available from the Safe Drinking Water Hotline.

When a contaminant is regulated based on concentration, there are three levels that are listed: 1) **Detection Limit for Report (DLR)**, 2) the **Public Health Goal (PHG)** or **Maximum Contaminant Level Goal (MCLG)**, and 3) the **Maximum Contaminant Level (MCL)**, **Action Level (AL)** or **Notification Level (NL)**.

The **DLR** is the smallest concentration of a contaminant that can be measured and reported. DLRs are set by DPH (same as MRL, Minimum Reporting Level, set by USEPA).

PHG and MCLG are the level of a contaminant in drinking water below which there is no known or expected risk to health. MCLGs are set by the USEPA. PHGs are set by Cal EPA.

A **Primary MCL** is the highest level of a contaminant that is allowed in drinking water. Primary MCLs are set as close to the PHGs (or MCLGs) as is economically and technologically feasible.

Secondary MCLs are set to protect the odor, taste, and appearance of drinking water.

ALs are Federal standards developed by USEPA that address the concentration of a contaminant which, if exceeded, triggers treatment or other requirements that a water system must follow.

NLs are State guidelines developed by DPH that address the concentration of a contaminant which, if exceeded, triggers public notification.

Treatment Technique: A required process intended to reduce the level of a contaminant in drinking water.

Maximum residual disinfectant level (MRDL): the level of a disinfectant added for water treatment that may not be exceeded at the consumer’s tap. MRDLs are set by the USEPA.

Maximum Residual Disinfectant Level Goal (MRDLG): the level of a disinfectant added for water treatment below which there is no known or expected risk to health.



CASTAIC LAKE
WATER AGENCY



CLWA SANTA CLARITA
WATER DIVISION



NEWHALL COUNTY-
WATER DISTRICT



VALENCIA WATER
COMPANY

REMEMBER:
Use Water Wisely, It's a Way of Life

Water conservation is both a local and a statewide concern. Conservation efforts at the local level can help “stretch” water supplies all over California. Californians should consider water conservation a way of life: water must be conserved in order for it to be available during cyclical droughts.

The SCV is an inland valley with a hot, dry summer and fall, often marked by high winds. The single greatest use of water in the Valley is landscape irrigation for residential lawns and gardens, commercial landscapes, parks, schoolyards, and golf courses.

Help Us Conserve Water this Summer

- **Check for Leaks.** Do you hear water running when no one is using it? Studies show that over 60% of Santa Clarita Valley households have leaks of up to 10 gallons a day, and 5% of those have leaks of 100 gallons per day.
- **Irrigate Wisely.** Outside water use is highest during the warmer months. Plants should not need watering more than three to four times per week. Visit H2ouse.org for more information on irrigation scheduling.
- **Mulch Your Garden.** It saves on evaporation and cuts down on weed growth.
- **Replace Your Old Toilet.** New models save greater than 50% compared to standard models. Call your water retailer and ask about the toilet replacement rebate they offer.

For more information about ways to conserve water, contact your water supplier or visit www.clwa.org.

FOR MORE INFORMATION

CASTAIC LAKE WATER AGENCY

David Kimbrough | (661) 297-1600 x223
E-mail: dkimbrough@clwa.org | Website: www.clwa.org
The Castaic Lake Water Agency is governed by a Board of Directors that meets on the second and fourth Wednesdays of each month at 6:30 pm, at the Rio Vista Administration Building, 27234 Bouquet Canyon Road.

CLWA SANTA CLARITA WATER DIVISION

Cathy Hollomon | (661) 259-2737
E-mail: chollomon@scwater.org | Website: www.clwa.org
The Santa Clarita Water Division is a division of the CLWA.

NEWHALL COUNTY WATER DISTRICT

Ryan Bye | (661) 259-3610
E-mail: rbye@ncwd.org | Website: www.ncwd.org
The Newhall County Water District is governed by a Board of Directors that meets on the second Thursday of each month at 6:30 pm, at the District Board Room, 23655 San Fernando Road, Suite “C”.

VALENCIA WATER COMPANY

James Saenz | (661) 294-0828
E-mail: jsaenz@valencia.com | Website: www.valenciawater.com
The Valencia Water Company is an investor-owned utility regulated by the California Public Utilities Commission. The office is located at 24631 Avenue Rockefeller.

Este informe contiene información muy importante sobre su agua beber. Si usted quisiera el texto en español para este reporte, comuníquese con David Kimbrough al numero de teléfono 661-297-1600 x223.



The Santa Clarita Valley

2008
Water
Quality
Report

The mission for the Castaic Lake Water Agency (CLWA) and local water purveyors is to provide reliable, quality water at a reasonable price to Santa Clarita Valley (SCV) residents. We are required by the California Department of Public Health (DPH) to publish an annual water quality report and much of the content is quite technical in nature and may inadvertently come across as daunting or ominous. The purpose of the 2008 Water Quality Report is to provide background on the quality of your water, ensuring your water meets or exceeds federal and state drinking water standards. If at any point in reviewing the document you have questions or concerns, please contact us at 661-297-1600, or visit us on the web at www.clwa.org.

Our Commitment to Water Quality—Each year thousands of water quality tests on surface and groundwater are conducted in the SCV. This report provides important information about the water sources, the composition of your water, and the steps taken to protect health and safety with water treatment process and water quality monitoring and testing.

All drinking waters contain some minerals or elements, often in very low levels. In water quality terms these substances are called contaminants. As water travels over the surface of the land or through the ground, it dissolves naturally-occurring minerals and, in some cases, radioactive material, and can pick up substances resulting from the presence of animals or from human activity.

Where your Water Comes From—The sources of drinking water include rivers, lakes, streams, ponds, reservoirs, springs, and wells. For our system, surface water comes primarily from the State Water Project (SWP) operated by the State Department of Water Resources, which is a 660 mile system of rivers, aqueducts and reservoirs that transports water from the Sierra Nevada to Southern California SWP contractors for use as agricultural or urban supply. CLWA’s SWP water is transported to Castaic Lake, and is later blended with groundwater. Our valley’s groundwater comes from local wells, some which tap into the shallow Alluvial Aquifer beneath the Santa Clara River and its tributaries and others which draw from the deeper Saugus Formation.



Help Us Conserve Water this Summer—2007 was one of the driest years on record for Southern California and specifically the SCV, and we will likely face more dry years in the future. As we meet and talk with SCV residents, more and more are expressing an interest in finding out how to incorporate simple water conservation practices into our everyday lives. Watch for easy tips on how to use water more efficiently, which in turn will help us provide reasonably priced water and ensure a dependable water supply for our future.

Water is one of our most valuable resources, and we are committed to serving you with reasonably priced water that meets and exceeds all state and federal health standards. Again, if you have any questions about this report, or water quality, please contact us at 661-297-1600, or visit us on the web at www.clwa.org. Additional information is available from local purveyors, whose contact information is supplied at the end of this report.

Sincerely,	Dan Masnada General Manager, CLWA	Steve Cole General Manager, NCWD
	Mauricio Guardado Retail Manager, SCWD	Robert DiPrimio President, VWC

NOTE: All of the test results in this report were run in 2007 unless noted otherwise. If you do not find a chemical listed in this report, it was not found in any test performed on local water. Your local water supplier is therefore in compliance with all drinking water regulations unless a specific violation is noted.

METALS AND SALTS

Metals and salts are tested in wells once every three years and in Castaic Lake water every month. Small quantities of naturally occurring arsenic are found in Castaic Lake and in a few wells. These are present due to the natural erosion of the rocks that waters travel over or through. Inorganic compounds such as salts and metals can be naturally occurring or result from urban storm water runoff, industrial or domestic wastewater discharges, oil and gas production, mining, or farming.

A number of naturally occurring salts are found in both surface and well water. These include chloride, fluoride, nitrate, nitrite, calcium, magnesium, potassium, and sodium. Taken together they are called Total Dissolved Solids (TDS). Calcium and magnesium together are called “hardness” and can deposit as scale.

Nitrate in drinking water at levels above 45 mg/L is a health risk for infants less than six months of age. High nitrate levels in drinking water can interfere with the capacity of the infant’s blood to carry oxygen, resulting in a serious illness; symptoms include shortness of breath and blueness of the skin. High nitrate levels may also affect the ability of the blood to carry oxygen in other individuals, such as pregnant women and those with certain specific enzyme deficiencies. Nitrate levels may rise quickly for short periods of time because of rainfall or agricultural activity. If you are pregnant or caring for an infant, you should ask for advice from your health care provider. Nitrates are tested at least annually.

DISINFECTION BY-PRODUCTS

Disinfection By-Products (DBPs), which include Trihalomethanes (THMs) and Haloacetic Acids (HAA5) are generated by the interaction between naturally occurring organic matter and disinfectants such as chlorine and ozone. THMs and HAA5 are measured at several points in each system and averaged once per quarter and reported as a running annual average.

The CLWA uses ozone to disinfect its water. Ozone is a very powerful disinfectant that not only kills organisms that no other disinfectant can but also destroys organic chemicals that causes unpleasant tastes and odors. However, ozone can also interact with bromide, a naturally occurring salt, to produce bromate. According to the USEPA and the California Department of Public Health (DPH) some people who drink water containing bromate in excess of the MCL over many years may have an increased risk of getting cancer. As a result, CLWA is required to analyze the water leaving its two treatment plants for bromate once per month under Federal regulations (State has also adopted D/DBP Rule).

Due to an oversight, in September 2006 CLWA did not collect or test samples for the presence of bromate as required and therefore cannot be sure of the bromate concentration of the water during that one month period. Short-term exposure to bromate is not considered a risk so there was no immediate health concern. Even though this failure was not an water quality emergency, we are required to notify our customers in accordance with Title 22, Division 4, Chapter 15, Article 18, Section 64463.7 of the California Code of Regulations and as our customers, you have a right to know what happened, what you should do, and what corrective actions were taken.

Since September 2006 CLWA has monitored for bromate in accordance with regulations and has purchased equipment to monitor bromate for itself at the CLWA Laboratory instead of contracting with an outside laboratory to perform this important analysis. Based on tests preceding September 2006 and all subsequent test results, CLWA has not exceeded the Federal standard for bromate.

There is nothing you need to do at this time. However, if you have health issues concerning the consumption of this water, you may wish to consult your doctor.

MICROBIOLOGICAL

Microbial contaminants, such as viruses and bacteria, can be naturally occurring or result from urban storm water runoff, sewage treatment plants, septic systems, agricultural livestock operations, and wildlife.

The most important microbiological drinking water tests are for bacteria. Water is tested for Total Coliform bacteria and for Escherichia coli (E. coli). The presence of E. coli indicates fecal contamination of waters. No E.coli was detected in any drinking waters in the SCV last year. Total coliforms are a group of bacteria that indicate water quality may have deteriorated. The MCL for total coliforms is 5% of all monthly tests showing positives for larger systems.

Additional microbiological tests for the water-borne parasites Cryptosporidium parvum and Giardia lamblia were performed on Castaic Lake water, and none were detected.

RADIOLOGICAL TESTS

Radioactive compounds can be found in both ground and surface waters, and can be naturally occurring or be the result of oil and gas production and mining activities. Testing is conducted for two types of radioactivity: alpha and beta. If none is detected at concentrations above five picoCuries per liter no further testing is required. If it is detected, the water must be checked for uranium and radium.

LEAD AND COPPER

The local water purveyors are required to sample for lead and copper at specific consumer taps. The results for lead and copper are reported as the 90th percentile. The 90th percentile is the result that is greater than 90% of all the results. Infants and young children are typically more vulnerable to lead in drinking water than the general population. It is possible that lead levels at your home may be higher than at other homes in the community as a result of materials used in your home’s plumbing. If you are concerned about elevated lead levels in your home’s water, you may wish to have your water tested and flush your tap for 30 seconds to two minutes before using tap water. Additional information is available from the USEPA Safe Drinking Water Hotline (800-426-4791).

ORGANIC COMPOUNDS

Organic chemical contaminants, including synthetic and volatile organic chemicals, are byproducts of industrial processes and petroleum production, and can also come from gas stations, urban storm water runoff, and septic systems. Organic compounds also include pesticides and herbicides, which may come from a variety of sources such as agriculture, urban storm water runoff, and residential uses. Water is tested for two types of organic compounds: Volatile Organic Compounds (VOCs) and Non-Volatile Synthetic Organic Compounds (SOCs). These organic compounds are synthetic chemicals produced from industrial and agricultural uses. Castaic Lake is checked annually for VOCs and SOCs. Local wells are tested at least annually for VOCs and periodically for SOCs. Tetrachloroethylene (PCE) was found in trace levels (below the MCL) in groundwater in the SCV. Some people who use water containing tetrachloroethylene in excess of the MCL over many years may experience liver problems, and may have an increased risk of getting cancer.

DRINKING WATER SOURCE ASSESSMENT AND PROTECTION

As part of DPH requirements, the purveyors of the SCV conducted a Drinking Water Source Assessment and Protection (DWSAP) study for all of their groundwater sources. This study enables DPH and water utilities to collect information about each drinking water source and surrounding residential, commercial, and industrial activities. It was completed and provided to DPH in 2002.

As part of the program, “surrounding activities” which include schools, medical offices, gas stations and various other facilities around each water source are categorized and ranked as “Possible Contaminating Activities” (PCA). Below is a list of PCAs that may have contributed to trace levels of contaminants in local wells.

- Automobile/gas stations, auto shops - tetrachloroethylene (PCE)
 - Dry cleaners - PCE
 - Known contaminant plumes - perchlorate
- Trace levels of PCE (below the MCL) have been detected in three wells.

In addition, a known perchlorate contaminant plume has been identified and several wells have tested positive for perchlorate. In October 2007, DPH adopted an MCL of 6 ug/L for this contaminant. Prior to October, a PHG of 6 ug/L and a Notification Level (NL) of 6 ug/L were established by the Office of Health Hazard Assessment and the DPH respectively.

In 2007, all of the surface water supplied to the SCV was provided by the SWP via Castaic Lake. The Department of Water Resources produces a watershed sanitary survey (WSS) of the SWP watersheds every five years. The last survey was published in 2001. Based on that WSS, a DWSAP study for Castaic Lake was completed in 2003. The study found that Castaic Lake supplies are considered to be most vulnerable to septic and sewage lift stations, recreational activities, boating, traffic accidents and spills, grazing livestock, algal blooms and fires.

Additional DWSAP information is available upon request from your local water purveyor. Contact names and numbers are supplied at the end of this report.

The Results of Thousands of Tests on Your Water

PARAMETERS/ CONSTITUENTS	Units	MCL (AL)	MCLG (PHG)	DLR	Castaic Lake Water Agency Wholesale Division			Castaic Lake Water Agency Santa Clarita Division			Valencia Water Company			Newhall County Water District Castaic			Newhall County Water District Newhall			Newhall County Water District Pinetree			Newhall County Water District Tesoro'		
INORGANICS RANGE					Minimum	Maximum	Typical	Minimum	Maximum	Typical	Minimum	Maximum	Typical	Minimum	Maximum	Typical	Minimum	Maximum	Typical	Minimum	Maximum	Typical	Minimum	Maximum	Typical
Aluminum	ug/L	1000	(60)	50	<DLR	129	<DLR	<DLR	<DLR	<DLR	<DLR	56.6	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	
Arsenic	ug/L	10	None	2	<DLR	2.7	<DLR	<DLR	<DLR	<DLR	<DLR	3.4	0.47	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	3.4	<DLR			
Fluoride²	mg/L	2	(1)	0.1	0.11	0.19	0.14	0.32	0.46	0.38	0.24	0.84	0.41	0.43	0.51	0.48	0.31	0.40	0.36	0.37	0.44	0.41			
Nitrate (as NO3)	mg/L	45	(45)	2	<DLR	3.4	2.6	11.2	36.4	20.4	6	31.3	16.8	<DLR	3.9	<DLR	7.1	28.3	17.7	14.0	18.0	16.0			
ORGANICS																									
Tetrachloroethylene³	ug/L	5	(0.06)	0.5	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	0.65	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	
DISINFECTION BY-PRODUCTS																									
Bromate RVTP	ug/L	10	0	5	<DLR	6.1	<DLR																		
Bromate ESFP	ug/L	10	0	5	<DLR	11	8.4																		
Haloacetic Acids (HAA5)	ug/L	60.0	0.0	1.0	1.8	6.6	4.4	0	35	6.3	0	13	4.8	1.4	13.0	5.5	<DLR	11.0	2.1	<DLR	6.8	4.6	<DLR	18.0	7.7
Trihalomethanes, Total (THMs)	ug/L	80.0	0.0	0.5	8.7	25.6	16.6	2.5	108	27.8	2.7	42.9	19.9	8.6	45.0	21.5	0.5	39.0	8.9	8.9	29.0	19.2	16.3	49.0	28.2
MICROBIOLOGICAL																									
Coliform % Positive Samples	%	5	0		0	1	0	0	0	0	0	2	0	0	1	0	0	1	0	0	1	0	0	1	0
CLARITY / TURBIDITY																									
Surface Water Only RVWTP	NTU	TT = 1 NTU	None		0.05	0.91	0.07																		
		TT = 95% of Samples < 0.2 NTU			99	100	100																		
Surface Water Only ESFP	NTU	TT = 1 NTU	None		0.05	0.19	0.08																		
RADIOLOGICAL																									
Alpha Activity, Gross	pCi/L	15	0	3	<DLR	1.8	<DLR	<DLR	5.3	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	6	1.7	<DLR	8	6.0			
Beta Activity, Gross	pCi/L	50	0	4	<DLR	3.8	<DLR																		
Radium 228	pCi/L	5	0	1	<DLR	<DLR	<DLR	<DLR	1.2	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR			
Uranium	pCi/L	20	(0.2)	2			NA	<DLR	4.4	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	<DLR	7.4	2.7			
Year of Analysis						2007			2005			2007			2005			2005			2005				
LEAD AND COPPER (Retailers Only)								90th Percentile	Tested	Above the AL	90th Percentile	Tested	Above the AL	90th Percentile	Tested	Above the AL	90th Percentile	Tested	Above the AL	90th Percentile	Tested	Above the AL	90th Percentile	Tested	Above the AL
Copper	ug/L	(1300)	(170)	50			NA	489	30	0	690	32	1	769	21	0	1121	31	2	1003	20	2	300	20	0
Lead	ug/L	(15)	(2)	5			NA	6	30	0	6	32	1	8.4	21	0	5.7	31	0	2.6	20	0	5.5	20	2
Year of Analysis									2006			2007			2006			2006			2006			2007	
SECONDARY STANDARDS					Minimum	Maximum	Typical	Minimum	Maximum	Typical	Minimum	Maximum	Typical	Minimum	Maximum	Typical	Minimum	Maximum	Typical	Minimum	Maximum	Typical			
Chlorides⁴	mg/L	250/500/600			41	67	58	41	91	71	25.2	102	58.63	60	63	61	40	45	43	17*	79*	54*			
Color	Units	15			<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5	<5			
Odor-Threshold	Units	3			1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1			
Sulfates⁴	mg/L	250/500/600			38	57	46	104	178	142	117	392	204	127	140	132	197	269	233	34*	94*	69*			
Turbidity	NTU	5			0.06	0.21	0.08	0.05	0.07	0.06	0.01	0.09	0.06	0.11	0.49	0.30	0.17	1.65	0.91	0.50	3.30	1.90			
Total Dissolved Solids⁴	mg/L	500/1000/1500			250	318	264	506	801	666	562	950	712	479	500	486	639	662	651	284*	614*	614*			
Conductivity⁴	uS / cm	900/1600/2200			445	479	445	840	1255	1091	835	1314	1033	818	851	837	992	1035	1014	452*	915*	726*			
ADDITIONAL TESTS																									
Calcium	mg/L				24	30	26	87	148	115	71	148	98	58	59	59	79	108	94	49*	88*	69*			
Magnesium	mg/L				12	14	13	21	48	32	20.4	42.4	30.5	21	23	22	14	25	20	14*	23*	18*			
Sodium	mg/L				37	51	44	65	93	77	46.2	109	76.6	65	73	69	51	96	73	47*	130*	101*			
Potassium	mg/L				2.4	3.1	2.6	1.8	4.9	3.4	1.75	4.2	3.19	3.4	4.4	3.8	2.1	2.6	2.4	3.3*	4.0*	3.5*			
Hardness as CaCO3	mg/L				108	128	116	305	504	416	269	540	370	232	240	236	255	375	315	183*	319*	249*			
pH	Units				7.58	8.02	7.80	7.24	7.65	7.5	7.2	7.57	7.43	7.50	7.90	7.64	7.23	7.44	7.34	7.42*	7.70*	7.52*			
Alkalinity as CaCO3	mg/L				76	89	82	215	308	281	168	257	221	162	180	170	142	206	174	149*	262*	216*			

Key for the Charts used in this Report

1 All values for Tesoro Water are the same as CLWA, except in the specific rows shown.

2 Depending on annual temperatures.

3 Some people who use water containing tetrachloroethylene in excess of the MCL over many years may experience liver problems, and may have an increased risk of getting cancer.

4 There are three MCLs for these parameters: The first is the recommended, long term. The second is the upper, long term. The third is short term.

*This data is from 2006; Annual analysis is not required for these constituents

AL Action Level
DLR Detection Limit for Reporting
ESFP Earl Schmidt Filtration Plant
MCL Maximum Contaminant Level
MCLG Maximum Contaminant Level Goal

ug/L Microgram / Liter
mg/L Milligram / Liter
mS Millisiemens
NTU Nephelometric Turbidity Units
NA Not Analyzed/Not Applicable

pCi/L Picocurie / Liter
PHG Public Health Goal
RVTP Rio Vista Treatment Plant